BRUHAT BANGALORE MAHANAGARA PALIKE

Dasarahalli Zone

Schedule-B

Name of work : Providing Sanitary line at missing bits repairs and replacement UGD lines in AGB and Surrounding area in ward no 12, Shettyhalli sub Division

Sl No	Description of Work	Unit	Qty as per Estimate	Rates	
				In Figures	In Words
1	Earthwork excavation for foundation to buildings, water supply, sanitary lines and eletrical conduits either in pits or in trenches 1.5m and above in width, In hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavatedstuff from edges of excavation with upto 50m including cost of explosives, labour and HOM of equipment complete as per specifications.	Cum	1804.88	299.98	Rupees Two Hundred Ninety Nine And Paise Ninety Eight Only
2	Providing and laying in position to required level or slope 230mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specifications.	Rmt	1015.00	554.38	Rupees Five Hundred Fifty Four And Paise Thirty Eight Only
3	Providing and laying in position plain cement concrete M7.5 40mm and down size graded granite metal, machine mixed concrete laid in layers not exceeding 15 cms thick, well compacted, for 230mm internal diameter stoneware pipes including cost of materials, labour charges, HOM of machinery, curing complete as per specifications	Rmt	875.00	493.96	Rupees Four Hundred Ninety Three And Paise Ninety Six Only
4	Constructing brick masonry circular type manhole 0.91m internal dia at bottom,1.67m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diametre confirming IS :12592, total weight cover and frame to be not less than 182 kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechineries complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid seperately)	No	36	22392.5	Rupees Twenty Two Thousand Three Hundred Ninety Two And Paise Fifty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bengaluru-57

5	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications	Cum	1804.88	134.62	Rupees One Hundred Thirty Four And Paise Sixty Two Only

Signature of Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahangara Palike,
Dasarahalli Division, Bengaluru-57